
HAWKINS

ROOFING

Quotation Ref : 6792.

Graham Bartlett.
11, Castle Street.
Thornbury.
Bristol BS35 1HA.

Date : 19th April 2026.

Site Address : No : As Above

Order Number :

Main Roof :

1. Erect Scaffolding to All Sides of the Property. - Sent Separate Email Containing Details.
£5,300.00
2. Strip All Roof Elevation of All Excising Materials.
3. Supply and Re - Felt and Batten All Roof Elevations with a Breathable Felt & 25 X 50 Treated Battens.
4. Supply and Fit All New Code 4 Lead to All Running Valleys.
5. Supply and Fit All New Code 4 Lead Soakers to All Parapet Walls.
6. Supply and Fit All New Code 4 Lead to All Stacks Sealing All Cover Flashings with a Lead Sealant.
7. Supply 40 % and Re - Tile All Roof Elevations with the Excising Clay Pan Tiles.
8. Supply 25 % and Re - Bed All the Excising Clay Ridge Tiles on Water Proof Sand & Cement.
9. Supply and Re - Make All Verges with New Under Cloak / Water Proof Sand & Cement.
10. Clear and remove all redundant materials from Site. £25,000
11. P.C Sum of £2,000 For Rafter / Timber Repairs.

Grand Total Amount £30,300.00 + v.a.t. @ 20

V.A.T Registration Number : 793 9601 83
91 WOODLEIGH GARDENS,WHITCHURCH, BRISTOL, BS14 9JG.
MOBILE : 07870 988284
